

SLAB REINFORCEMENT SCHEDULE

PROJECT: Cantilever Retaining Wall — 4m High | DATE: 2026-06-14 | CODE: EN 1992-1-1:2004

MARK	h (mm)	SPAN (m)	T-X	T-Y	B-X	B-Y	As,bot (mm ² /m)	UTIL	STATUS	N
BASE	500	3.8	H16@150	H16@150	H20@150	H20@150	2094	<div><div style="width: 58%;"></div></div> 58%	PASS	1

TOTAL REINFORCEMENT (indicative): 778.698 t | 1 slab type(s) | Spec: EN 1992-1-1 | Grade: B500B